

Republic of the Philippines Department of Justice

BUREAU OF CORRECTIONS

Muntinlupa City



SUPPLEMENTAL BID BULLETIN NO. 2

DESIGN AND BUILD OF BUREAU OF CORRECTIONS REGIONAL FACILITY AT IPPF - PHASE 2

(ITB NO. 2024-020)

FOR

ALL PROSPECTIVE BIDDERS AND OBSERVERS

FROM

BIDS AND AWARDS COMMITTEE

RE

AMENDMENTS ON BIDDING DOCUMENTS

DATE

22 MAY 2024

Please be informed with the amendments on the bidding documents as follows:

A. Section VI. Specifications (Scope of Works):

Original Text		Amended/Additional Text	
	Section 1.1c (Project Description and Section 3.2- VII (Construction Phase):		Section 1.1c (Project Description and Section 3.2- VII (Construction Phase):
1 unit	One (1) Storey Type 'B' PDL Dormitory Building with 500 PDL Capacity. 4.7sqm per PDL (shower, water closet and wash basin included). Maximum of 10PsDL per cell.	1 unit	Two (2) Storey Type 'B' PDL Dormitory Building with 500 PDL Capacity. 4.7sqm per PDL (shower, water closet and wash basin included). Maximum of 10PsDL per cell.
	Including: Fire Protection and Fire Detection Alarm Systems, and Fire suppression equipment for Dormitory in accordance to governing laws and regulations requirements. (Fire house, jockey pumps and firepumps)		Including: Fire Protection and Fire Detection Alarm Systems, and Fire suppression equipment for Dormitory in accordance to governing laws and regulations requirements. (Fire house, jockey pumps and fire pumps)
	With Stainless Steel Elevated Water Tank on roof deck; to supply sufficient pressure in every plumbing fixtures. Minimum number of fixtures per cell: 2 unit's flush valve water closet, 2 unit flush valve urinal, 1 unit lavatory, 3 units wall faucet, and 3 units shower head.		With Stainless Steel Elevated Water Tank on roof deck; to supply sufficient pressure in every plumbing fixtures. Minimum number of fixtures per cell: 2-unit's flush valve water closet, 2-unit flush valve urinal, 1unit lavatory, 3 units wall faucet, and 3 units shower head.

	Provide enhanced natural ventilation as necessary.		Provide enhanced natural ventilation as necessary.
1 unit	Partition Security Fence between existing dormitory building and new dormitory	1 lot	Partition Security Fence between existing dormitory building and new dormitory-building
1 unit	One (1) storey infirmary Building (600sqm)	1 unit	One (1) storey infirmary Building (600sqm)
1 unit	One (1) storey Visitation Area 1,040sqm, (office, control/frisking area, toilets).	1 unit	One (1) storey Visitation Area 200sqm, (office, control/frisking area, toilets).
1 unit	Main Security Gate and 60 sqm Security Office	1 unit	Primary Security Gate with 60 sqm Security Office
1 unit	Secondary Security Gate	1 unit	Secondary Security Gate
1 lot	Site Development. Includes not limited to the following: Stormwater Management: Implementing systems to manage stormwater runoff, which include underground drainage systems. (planning, designing, and installing pipes, channels, culverts, ditches, and other structures that collect, convey, and discharge storm water runoff). Drainage outfall to connect to existing nearest drainage line. Shall Conform to existing rules and regulations of the LGU. Grading and Earthwork: Leveling the	1 lot	Site Development Plan (Earthworks/Grading, Drainage)
	ground and shaping it to the required specifications for the construction project. This may involve excavation, filling, and compacting soil.	,	
250 units	Double Deck Bunk Beds (design and specification of Bunk Beds for review of Planning and Design Unit – GSD).	250 units	Double Deck Bunk Beds (design and specification of Bunk Beds for review of Planning and Design Unit – GSD).
1 lot	Water supply system. Includes the ff: water source, storages, distribution and plumbing system. Sufficient water pressure to supply outpost plumbing fixtures		Utilities, Sanitation and Miscs
1 lot	Three-phase Power line supply (designed to supply the entire compound including the future developments). Connected From	1 lot	Three-phase Power line supply (designed to supply the entire compound including the future developments). Connected From

	Electric local utility to security compound (project site)		Electric local utility to security compound (project site)
1 lot	Backup Power supply system with capacity not less than the total computed MVA load, without demand factor. (designed to supply the entire compound including the future developments).	1 lot	Backup Power supply system (GenSet) with capacity not less than the total computed KVA load, without demand factor. (designed to supply the two dormitory plus Power House).
1 lot	CCTV system for dormitory (centralized). Recording of video data will be continuous 24/7/365 for all cameras deployed on the Security Video System. Provision of housing for protection of outside CCTVs. With IR LEDs for true day and night surveillance. With at least 2MP sensor. With wide field of vision. With movement sensor.	1 lot	CCTV system for dormitory (centralized). Recording of video data will be continuous 24/7/365 for all cameras deployed on the Security Video System. Provision of housing for protection of outside CCTVs. With IR LEDs for true day and night surveillance. With at least 2MP sensor. With wide field of vision. With movement sensor.

****Contractor must have a valid PCAB license with AAAA category.

Pursuant to Section 22.5 of the 2016 Revised Implementing Rules and Regulations of Republic Act No. 9184, this Supplemental/Bid Bulletin is issued for the information and guidance of all prospective bidders and shall form an integral part of the Bidding Documents issued for said the project.

Should you have further concerns, you may contact the BAC Secretariat through the details below:

MARIA ADORACION I. VIÑAS

Head, Bids and Awards Committee Secretariat

Bureau of Corrections

Supply Division, New Bilbid Prison Reservation

Tel. No. (+632)8659-0833

Email: bacsec2022@gmail.com

Website: https://www.bucor.gov.ph

For information and guidance.

C/CSUPT CELSO S BRAVO

Chairperson, Bids and Awards Committee